



ASSURING QUALITY HOMES

**REQUEST FOR PROPOSAL: APPOINTMENT OF A SERVICE PROVIDER TO REPAIR
WINDOWSILLS AND REPAIR THE AIRCONDITION VENT COVERS AT NHBRC BUILDING IN
SUNNINGHILL**

1. REPAIR WINDOWSILLS:

Remove defective windowsills. Reapply damp-proof course with new windowsills.

Supply and install new windowsills.

Number of Windowsills = 38 Dimensions = L x W x B = 3100 mm x 245mm x 15mm

Number of Windowsills = 4 Dimensions = L x W x B = 1830 mm x 245mm x 15mm

Remove the peeling off rhino lite on 10 pillars. (H 1,39m x W 0,50cm x B 0,56cm).

Apply new rhino lite and repaint the pillars.

Repair and paint the damaged wall, dimensions are (Length 3.9m x Height 2.4m).

Repair Ceiling in the passage ground floor (Length 3.9m x Width 1.4m)

Seal the windows on the lift shaft.





ASSURING QUALITY HOMES

2. REPAIR THE AIR-CONDITION VENT COVERS:

Remount the wobbly grill covers around the building.

Dimensions : 1.2m length x 61cm height.

East side : 4 fall down

South side : 15 that are wobbly

North side : 3 fall down

NB: Utilise the Cherry Picker to execute the task to ensure that all windows are sealed.



NB: THIS WORK MUST BE DONE ON WEEKENDS OR AFTER WORKING HOURS.

Developed by: Andile Nyubatya

Checked by: Fanele Majoji

Approved by: Joshua Hadebe

Signature:  Date: 19/07/2023

