

**ASSURING QUALITY HOMES** 

REQUEST FOR PROPOSAL: APPOINTMENT OF A SERVICE PROVIDER TO SUPPLY, INSTALL AND MAINTAIN A 60KVA DIESEL STANDBY GENERATOR AT NHBRC SITE IN ERIC MOLOBI LABORATORY(SOSHANGUVE).

1. SCOPE OF WORK: SUPPLY, INSTALLATION AND MAINTAIN STANBY GENERATOR FOR PERIOD OF TWELVE (12) MONTHS

Date: August 2023 BOQ Ref: EM01/08/23

FEATURES
1.1. Preferred Make: Deutz or Perkins
1.2. Maximum 66KVA, 380V, 1500RPM
1.3. 24Volt Electric starter
1.4. Leroy Alternator
1.5. 125 Litre Fuel tank, 14hours @ 75% load
1.6. Silent weather resistant canopy
1.7. Four cylinder, turbo & intercooled, water cooled Diesel engine
1.8. 3 Phase output
1.9. 12 months or 1000hrs warranty
1.10. Installation cost (on concrete base), transport & consumables
TOTAL:

NB: COC required on completion, installation to be done by authorized installer

Please provide separately diesel rate per liter for period of 12 months as in when required.

Approved by: Kgosi Mashaba

Signature: Malhada

**Date**: 14 August 2023

