

1. EXTENT OF CONTRACT

Building contract

The work embodied in the contract comprises remedial work for flat roofs of common property, at 49 Silver Oaks Avenue, Essenwood Berea, Durban

The successful tenderer for this contract will be appointed in terms of the National Home Builders Registration Council Remedial work.

2. ACQUAINTANCE WITH TENDER DOCUMENTS

By submission of a tender, the contractor shall be deemed to have acquainted himself with the contract documents, local requirements and laws and all aspects of the work envisaged in the documents, prior to pricing and submission of a tender. It is of vital importance that the tenderers visit the site prior to the submission of a tender to study conditions on site.

No claim resulting from failure to comply with any of the above will be entertained.

3. CONTRACT DOCUMENTS

The contract documents shall comprise:

- * Bill of Quantities
- * Engineer's scope of work

4. BILLS OF QUANTITIES

These Bill of Quantities to be priced in accordance with the scope of works, with all the quantities being provisional and are to be re measured on completion of the project.

For the purpose of this Bill Of Quantities, the following words shall have meanings hereby assigned to them:

Unit-The unit of measurement for each item of work as defined in the specifications

Quantity- The number of units of work for each item

Rate- The payment per unit of measurement at which the tenderer tenders to do the work

Amount- The product of the quantity and the rate tendered for an item

The quantities set out in the Bill Of Quantities are provisional quantities only. Quantities to be re-measured on site and paid accordingly.

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

The validity of the contract shall in no way be affected by differences between the quantities in the Bill of Quantities and the quantities finally certified for payment. Work shall be valued at the rates tendered.

The units of measurement indicated in the Bill Of Quantities are metric units

The following abbreviations are used in the Bill Of Quantities:

mm	= millimeter
m	= metre
m ²	= square metre
m ³	= cubic metre
no	= number
%	= percent

All rates and sums of money quoted in the Bill Of Quantities shall be in rands and whole cents. Fractions of a cent shall be discounted

These Bills Of Quantities contain pages numbered consecutively as indicated in the Index. Before the contractor submits his tender he should check the number of pages, and if any are found to be missing or duplicated, or the figures or writing indistinct, or the tender documents contain any obvious errors, he should apply to the quantity surveyors at once and have same rectified as no liability whatsoever will be admitted by the National Home Builders Registration Council (NHBRC) in respect of errors in a tender due to the foregoing.

On no account should these documents be used for placing orders for materials. The contractor may do so at his own risk but shall not be reimbursed for additional costs so incurred.

Unless a separate rate for the supply and for the installation of any items is specifically called for, the supply and installation costs of any item shall be deemed to be fully included in the unit price.

5. MATERIAL AND LABOUR COST FLUCTUATIONS

All rates in this tender shall be fixed for the duration of the contract.

6. CONDITIONS TO BE OBSERVED IN TENDERING

- 6.1 Tenders shall include Value Added Tax
- 6.2 The Conciliation Officer will notify the tenderers of the tender results
- 6.3 The lowest, or any, or portion of any tender will not necessarily be accepted.
- 6.4 All tender prices/rates must be filled in on the form provided.

**Section No.
NOTES AND SPECIFICATIONS
NOTES TO TENDERERS
PROVISIONAL BILL OF QUANTITIES
NHBRC REMEDIAL WORK**

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

6.5 Tenders prices/rates must hold good for thirty (90) calendar days from the tender closing date as stated herein.

6.6 All recipients of the tender document (whether they submit a tender or not) must treat the details of the document as private and confidential

6.7 The employer will not be responsible for, or pay for, expenses or losses, which may be incurred by any tenderer in the preparation of his tender.

7. TENDER INFORMATION

The employer may require additional information from the tenderer in order to evaluate the tender. The tenderer is required to provide such information if so required by the employer.

8. SITE INSPECTION

The compulsory site visit date will be communicated to the tenderers.

The tenderer is also required to familiarise himself before submission of his tender with regard to relevant local site conditions, site accessibility, the nature of operations required, availability of labour and any conditions pertaining there to, together with conditions relating to unloading, carting and storage of materials, equipment and tools required for the works.

**Section No.
NOTES AND SPECIFICATIONS
NOTES TO TENDERERS
PROVISIONAL BILL OF QUANTITIES
NHBRC REMEDIAL WORK**

NAMES OF PARTIES

- 1. EMPLOYER**
National Home Builders Registration Council
Contact Person: Mr Songezo Boo
Physical Address: 27 Leeuwkop Road, Sunninghill, Johannesburg
Postal address: P O BOX 461, Randburg, 2125
Tel: (011) 317-0000
Fax: (011) 317-0105

- 2. ENGINEER**

National Home Builders Registration Council
Contact Person: Dr Siphon Thango
Physical Address: Royal Towers, 30 Dorothy Nyembe street,
Durban Central
Tel: (031) 374-8100

- 3. CONCILIATION OFFICER**

National Home Builders Registration Council
Contact Person: Mr Andile Zulu
Physical Address: Royal Towers, 30 Dorothy Nyembe street
Durban Central, KwaZulu Natal
Tel: (031) 374-8100

- 4. QUANTITY SURVEYOR**

National Home Builders Registration Council
Contact Person: Mr Moseo Sebetha
Physical Address: 27 Leeuwkop Road, Sunninghill, Johannesburg
Tel: (011) 317-0006

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 1</u></p> <p><u>PRELIMINARIES AND GENERALS</u></p> <p><u>NOTES</u></p> <p>The agreement is to be a "Remedial work contract agreement" that will be signed between the Employer (NHBRC) and Contractor upon acceptance to tender offer</p> <p><u>Temporary works and plant</u></p> <p>The contractor shall protect, uphold and maintain all public utilities and services and shall not interfere with their operation without the consent of the service authorities and the principal agent. The contractor shall notify the Principal Agent of any damage to such services and shall make good same at his own cost to the satisfaction of the service authorities</p> <p>Fuel, power and water for commissioning of mechanical and other specialised equipment shall also include for the cost of all necessary reticulation and connections thereto</p> <p>The contractor shall provide noise and dust control to the approval of the Principal Agent</p> <p>The contractor shall maintain the access roads, paths, buildings, etc, adjacent to the construction area etc, during the period of the works in a clean and rubble free condition</p> <p><u>Identity of employees</u></p> <p>All employees of the contractor and his sub contractors shall be identifiable at all times by means of ID cards, company name and logos imprinted on overalls. Any person found on site not complying with the abovementioned conditions the contractor shall be requested by Principal Agent, to remove such person from the site</p> <p style="text-align: right;">Carried forward</p>			
	<p>Section No. 1</p> <p>BUILDINGS</p> <p>Bill No. 1</p> <p>PRELIMINARIES AND GENERALS</p> <p>PROVISIONAL BILL OF QUANTITIES</p> <p>NHBRC REMEDIAL WORK</p>		R	

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

	Brought forward		R
	<p><u>Health and Safety</u></p> <p>The contractor is to comply with all requirements of the Health and Safety Specification</p> <p><u>Housekeeping and compliance with Principal agent site rules</u></p> <p>The contractor will be responsible for a high standard of housekeeping in his site establishment, delivery of materials and goods and removal of rubble, debris, etc, storage areas and construction working areas to the approval of the Principal Agent</p> <p><u>Working Hours</u></p> <p>Should the contractor wish to work outside normal working hours or at weekends in order to maintain his building programme, he shall notify and obtain the approval from the Principal Agent before doing so. The cost of this overtime will be for the contractor's account</p> <p><u>All risk insurance</u></p>		
1	Allowance for contractor's all risk insurance	Item	
	<p><u>Health and Safety</u></p>		
2	Allowance for all health and safety requirements as deemed necessary for the successful execution of the project	Item	
	<p><u>Management of contract</u></p>		
3	Management of the works, programming for the works, progress meetings, technical meetings, etc	Item	
	<p>A : 0.00 B : 0.00 C : 0.00 D : 0.00</p> <p>E : 0.00 F : 0.00 G : 1.00 H : 0.00</p>		
	<p><u>Temporary works and plant</u></p>		
4	Plant, equipment, scaffolding, sheds and offices etc	Item	
	<p><u>Temporary Services</u></p>		
5	Water, electricity, telecommunication equipment, ablution facilities, etc	Item	
	Carried forward		R
	<p>Section No. 1 BUILDINGS Bill No. 1 PRELIMINARIES AND GENERALS PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>		

**NHBRC-REMEDIAL WORKS-
 SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
 49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
 DURBAN, KWA-ZULU NATAL**

	Brought forward		R
<p><u>House Keeping</u></p>			
<p>6 Allowance for housekeeping and compliance of unwanted material to be dumped and disposed to a site designated by local authority</p>	Item		
<p style="text-align: right;">Carried Forward to Sectional Summary: 1</p> <p>Section No. 1 BUILDINGS Bill No. 1 PRELIMINARIES AND GENERALS PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>			R

NHBRC-REMEDIAL WORKS-
 SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
 49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
 DURBAN, KWA-ZULU NATAL

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 2</u></p> <p><u>ALTERATIONS</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting the tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained.</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated</p> <p><u>General</u></p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with minimum of disturbance to adjoining premises and their tenants. He/she shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the engineer.</p> <p>Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the engineer.</p> <p style="text-align: right;">Carried forward</p> <p>Section No. 1 BUILDINGS Bill No. 2 ALTERATIONS. PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>		R	

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

		Brought forward		R
<p>Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before refixing including taking off. easing and rehangng, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all ail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately</p> <p>Prices for taking out doors, windows, etc shall including for removal of all beads, architraves, ironmongery, etc</p> <p>Prices for taking out and removing doors and frames shall include for removing door stop, cabin hook, etc and making good floor and wall finishes to match existing</p> <p>With regard to building up of openings in existing walls, cement screeds and pavings, granolithis, tops of walls, etc, shall be levelled and prepared for raising of brickwork</p> <p>Making good of finishes shall include making good of the brick and concrete surfaces onto which the new finishes are applied, where necessary</p> <p><u>LEGEND</u></p> <p><u>REMOVAL OF EXISTING WORK</u></p> <p><u>Taking out and removing sundry joinery work, fittings, etc</u></p>				
1	<p>Cupboard type 2613 x 600 x 2700mm including backboards, etc</p> <p style="margin-left: 40px;">A : 3 B : 7 C : 8 D : 3</p> <p style="margin-left: 40px;">E : 8 F : 8 G : 0 H : 0</p>	m	35	
2	<p>Cupboard type 3900 x 600 x 600mm including backboards, etc</p> <p style="margin-left: 40px;">A : 4 B : 0 C : 0 D : 0</p> <p style="margin-left: 40px;">E : 0 F : 0 G : 0 H : 0</p>	m	4	
		Carried forward		R
<p>Section No. 1 BUILDINGS Bill No. 2 ALTERATIONS. PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>				

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

		Brought forward		R
3	Cupboard type 3900 x 400 x 400mm including backboards, etc A : 4 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	4	
4	Cupboard type 3000 x 400 x 600mm including backboards, etc A : 3 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	3	
5	Cupboard type 3000 x 400 x 400mm including backboards, etc A : 3 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	3	
6	Timber Skirting A : 0 B : 0 C : 0 D : 0 E : 0 F : 13 G : 0 H : 0	m	13	
<u>Taking down and removing roofs, floors, panelling, ceilings, partitions, etc</u>				
7	Gypsum plasterboard ceilings, including cornices, timber bandering, etc A : 0 B : 0 C : 17 D : 0 E : 17 F : 0 G : 0 H : 0	m2	34	
<u>Hacking up/off and removing ceramic tiles including removing mortar bed or adhesive from concrete or brickwork and preparing surfaces for new screed, plaster, tile finishes, etc</u>				
8	Tiles to walls A : 56 B : 0 C : 28 D : 0 E : 28 F : 0 G : 0 H : 0	m2	112	
Carried Forward to Sectional Summary: 1				R
Section No. 1 BUILDINGS Bill No. 2 ALTERATIONS. PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK				

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 3</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere</p> <p><u>Joinery</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p> <p>Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts</p> <p><u>Decorative thermosetting plastic laminate covering</u></p> <p>Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish</p> <p><u>FITTINGS</u></p> <p><u>CUPBOARDS TO KITCHENS, BEDROOMS, ETC</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>General</u></p> <p>The following cupboard fittings have been given as complete units i.e. the components of the units have not been given separately. Descriptions of such units shall, therefore, be deemed to include all components, assembling, housing, notching, glueing, blocking, planting-on and screwing with countersunk screws, edge strips, thermosetting plastic laminate, glass, ironmongery, metalwork, paint or varnish finishes, etc</p> <p style="text-align: right;">Carried forward</p> <p>Section No. 1 BUILDINGS Bill No. 3 CARPENTRY AND JOINERY PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>			R

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

		Brought forward		R
Prices are to include for all necessary filler pieces against walls etc				
<u>Bedroom cupboards etc</u>				
<u>Bedroom cupboards etc with hinges, handles, cupboard locks to doors, and clothes hanging rails in hanging spaces, etc</u>				
1	Cupboard type 2613 x 600 x 2700mm including backboards, etc A : 3 B : 7 C : 8 D : 3 E : 8 F : 8 G : 0 H : 0	m	35	
2	Cupboard type 3900 x 600 x 600mm including backboards, etc A : 4 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	4	
3	Cupboard type 3900 x 400 x 400mm including backboards, etc A : 4 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	4	
4	Cupboard type 3000 x 400 x 600mm including backboards, etc A : 3 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	3	
5	Cupboard type 3000 x 400 x 400mm including backboards, etc A : 3 B : 0 C : 0 D : 0 E : 0 F : 0 G : 0 H : 0	m	3	
6	Timber Skirting A : 0 B : 0 C : 0 D : 0 E : 0 F : 13 G : 0 H : 0	m	13	
Carried Forward to Sectional Summary: 1				R
Section No. 1 BUILDINGS Bill No. 3 CARPENTRY AND JOINERY PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK				

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 4</u></p> <p><u>CEILINGS, PARTITIONS AND FLOORING</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere</p> <p><u>Ceilings</u></p> <p>Unless otherwise described ceilings shall be deemed to be horizontal</p> <p><u>Bulkheads</u></p> <p>Bulkheads are defined as those portions of ceilings which are stepped down from the general ceiling level in a particular room or area and which generally occur along the perimeter. Their purpose is either to conceal services or to create architectural features</p> <p>Bulkheads have only been described as such where they conform to the above definition and where the horizontal or vertical dimensions do not exceed 900mm. Where these dimensions are more than 900mm such portions of ceilings have been included in the appropriate general items of ceilings</p> <p>Unless otherwise described bulkheads shall be deemed to be horizontal along the length</p> <p>Steel components</p> <p style="text-align: right;">Carried forward</p> <p>Section No. 1 BUILDINGS Bill No. 4 CEILINGS, PARTITIONS AND FLOORING PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>			
			R	

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

<p style="text-align: right;">Brought forward</p> <p>All steel components for ceilings, partitions, etc are to be galvanised in accordance with SANS 121</p> <p><u>User note</u></p> <p><i>Circular bulkheads shall be given separately</i></p> <p><u>NAILED-UP CEILINGS</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Openings</u></p> <p>Prices for openings for light fittings, ventilation grilles, air conditioning diffusers, etc are to include for any necessary additional support, trimming around, etc</p> <p><u>SUSPENDED CEILINGS</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary suspended ceilings</u></p> <p>Hangers, suspension grids, "lay-in" panels, etc are to be in accordance with the manufacturers' recommendations</p> <p><u>Flush plastered gypsum plasterboard suspended ceilings</u></p> <p>Ceilings shall comprise 6,4mm (9,5mm? 12,5mm?) gypsum plasterboard boards screwed to and including screw-up suspension grid consisting of main tees at 1 200mm centres and galvanised steel capped cross tees at 400mm centres and with tape fixed over joints and the whole finished with gypsum plaster trowelled to a smooth polished surface</p> <p>The grid shall be suspended by means of galvanised steel L-section hangers at suitable centres, securely shot-pinned or screwed to concrete, steel or wood</p>		R	
<p style="text-align: right;">Carried forward</p> <p>Section No. 1 BUILDINGS Bill No. 4 CEILINGS, PARTITIONS AND FLOORING PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>		R	

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

Brought forward					R
<p><u>Flush plastered gypsum plasterboard suspended bulkheads</u></p> <p>Bulkheads shall comprise galvanised steel studding of 63,5mm top and bottom tracks with vertical studs at maximum 400mm centres, pop-riveted to the top and bottom tracks with similar additional vertical studs as necessary at abutments, ends, etc and covered as described with plasterboard screwed to studding with drywall screws at maximum 300mm centres. Boards shall be butt Jointed and finished with tape and jointing compound and the whole finished with gypsum plaster trowelled to a smooth polished surface to the thickness recommended by the manufacturer</p> <p>Descriptions shall be deemed to include any additional studs at ends and intersections, corner beads, cornices at junctions with ceilings, jointing compound, tape, etc</p> <p><u>Gypsum plasterboard on screw-up tee suspension grid including hangers etc, with tape fixed over joints and the whole finished with gypsum plaster trowelled to a smooth polished surface</u></p>					
1	Ceilings		m2	34	
	A : 0 B : 0 C : 17 D : 0				
	E : 17 F : 0 G : 0 H : 0				
2	Cornice		m	48	
	A : 0 B : 0 C : 24 D : 0				
	E : 24 F : 0 G : 0 H : 0				
Carried Forward to Sectional Summary: 1					R
<p>Section No. 1 BUILDINGS Bill No. 4 CEILINGS, PARTITIONS AND FLOORING PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>					

NHBRC-REMEDIAL WORKS-
 SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
 49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
 DURBAN, KWA-ZULU NATAL

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 5</u></p> <p><u>TILING</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions</u></p> <p>Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding</p> <p>Tiling described as "fixed with adhesive on power floated concrete" shall be deemed to include for approved tiling key-coat</p> <p>Ceramic, porcelain, marble and granite tiles are to be fixed and grouted with suitable adhesives and grouts from the "Tal Professional" ("Ceresit Tylon"?) range of products as recommended by the manufacturer of the tiles</p> <p><u>WALL TILING</u></p> <p><u>Wall tiles (To match existing) (PC R 250/m2 fixed with adhesive on to walls (Including the treating of walls with bonding liquid) and flush pointed waterproofing grout.</u></p>			
1	<p>On walls</p> <p>A : 56 B : 0 C : 28 D : 0</p> <p>E : 28 F : 0 G : 0 H : 0</p>	m2	112	
	<p style="text-align: right;">Carried Forward to Sectional Summary: 1</p> <p>Section No. 1 BUILDINGS Bill No. 5 TILING PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>		R	

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 6</u></p> <p><u>PAINTWORK</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p><u>Previously painted wood surfaces</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with Plascon specifications unless otherwise described</p> <p><u>COLOURS</u></p> <p>Unless otherwise described all paintwork shall be deemed to have a colour value in excess of 7 on Munsell system in accordance with SANS 1091</p> <p><u>PAINTWORK ETC TO PREVIOUSLY PAINTED WORK</u></p>			
	Carried forward		R	
	<p>Section No. 1 BUILDINGS Bill No. 6 PAINTWORK PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>			

		Brought forward		R
		<u>ON INTERNAL FLOATED PLASTER SURFACES</u>		
		<u>Prepare and apply two coats interior high quality acrylic paint to match existing</u>		
1	On internal walls	m2	399	
	A : 80 B : 39 C : 99 D : 31			
	E : 99 F : 51 G : 0 H : 0			
		<u>ON PLASTER BOARD</u>		
		<u>Prepare and apply two coats high quality acrylic paint on work in sound condition to match existing.</u>		
2	Ceilings including cornices, etc	m2	74	
	A : 0 B : 35 C : 0 D : 38			
	E : 0 F : 0 G : 0 H : 0			
		Carried Forward to Sectional Summary: 1		R
		Section No. 1		
		BUILDINGS		
		Bill No. 6		
		PAINTWORK		
		<i>PROVISIONAL BILL OF QUANTITIES</i>		
		<i>NHBRC REMEDIAL WORK</i>		

NHBRC-REMEDIAL WORKS-
 SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
 49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
 DURBAN, KWA-ZULU NATAL

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 7</u></p> <p><u>PROVISIONAL SUMS</u></p> <p><u>General</u></p> <p>Work for which budgetary allowances are provided will be measured and valued in accordance with clause 32 of the Principal Building Agreement and deducted in whole or in part if not required without any compensation for loss or profit on the said allowances</p> <p>Prime cost amounts and provisional sums are net. Prime cost amounts include for delivery to site of all articles concerned</p> <p>Provisional sums are for material and equipment supplied and installed complete by firms of specialists</p> <p><u>Profit</u></p> <p>Where stated, the contractor may allow for profit if required</p> <p><u>General attendance on nominated/selected subcontractors</u></p> <p>The item "Attendance" which follows each provisional sum for nominated/selected subcontractors' work, shall be deemed to cover all the contractor's costs incurred in providing free of charge to the nominated/selected subcontractors, the following:</p> <p>1 Making good in all trades and cleaning down and removal of rubbish on completion</p> <p>Special attendance on nominated/selected subcontractors</p> <p style="text-align: right;">Carried forward</p> <p>Section No. 1 BUILDINGS Bill No. 7 PROVISIONAL SUMS PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK</p>			
			R	

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

		Brought forward	R
	<u>Builder's work</u>		
	Builder's work in connection with specialist services is given elsewhere in these bills of quantities		
	<u>General Demolition, etc</u>		
1	Allow the amount of R 30 000 (Thirty Thousand Rand) for general demolitions, etc	Item	
2	Profit	%	
3	Attendance	%	
	Carried Forward to Sectional Summary: 1		R
	Section No. 1 BUILDINGS Bill No. 7 PROVISIONAL SUMS PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK		

**NHBRC-REMEDIAL WORKS-
SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
DURBAN, KWA-ZULU NATAL**

Bill No	Section No. 1 BUILDINGS <u>SECTION SUMMARY - BUILDINGS</u>	Page No	Amount
1	PRELIMINARIES AND GENERALS	7	-----
2	ALTERATIONS.	10	-----
3	CARPENTRY AND JOINERY	12	-----
4	CEILINGS, PARTITIONS AND FLOORING	15	-----
5	TILING	16	-----
6	PAINTWORK	18	-----
7	PROVISIONAL SUMS	20	-----
Carried to Final Summary			R
Section No. 1 BUILDINGS PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK			

**NHBRC-REMEDIAL WORKS-
 SILVER OAKS COMPLEX - (UNITS 101, 104,201,204,301,304)
 49 SILVER OAKS AVENUE, ESSENWOOD,BEREA
 DURBAN, KWA-ZULU NATAL**

Section No	<u>FINAL SUMMARY</u>	Page No		Amount
1	BUILDINGS	21		
	SUB TOTAL		R	
	<u>CONTINGENCY</u>			
	Allow a contingency of 10% to be used as directed by the Quantity Surveyor.		SUM	
	VALUE ADDED TAX		R	
	Carried to Form of Tender		R	
	PROVISIONAL BILL OF QUANTITIES NHBRC REMEDIAL WORK			